

BRUHATH BENGALURU MAHANAGARA PALIKE
Yelahanka Division, Yelahanka Zone

Executive Engineer
Yelahanka Division
B.B.M.P. Bengaluru - 64

APPROVED TENDER SCHEDULE - 'B'

No.EE/YNK-D/E-PMT/06/2013-14 Dated: 06-11-2013

Item No: 67

Name of Work: -Providing of BS slab drain at Ambha bhavani temple road from Sambam college to Subhash Chandra Bose road in Attur, ward no:03

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri K CHANNAKESHAVAMURTHY	
				Rate	Rate in Words
1	KSRB 2-2-2:Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications Specification	Cum	396.66	200.00	Rupees two hundred only
2	Providing 7.5 cm thick granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete	Sqm	1476.00	315.00	Rupees three hundred fifteen only
3	KSRB 4-1-3:Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180 kgs. with 40mm and down size graded granite metal coarse aggregates @ 0.85 cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not exceeding 15 cms, thick well compacted, in foundation and plinth including cost of all materials, labour, H.O.M of machinery, curing complete as per specifications. Specification	Cum	15.22	4000.00	Rupees four thousand only
4	KSRB 5-2-3:Providing and constructing granite / trap / basalt size stone masonry in foundation cement mortar 1:5 stone hammered dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.	Cum	38.15	3300.00	Rupees three thousand three hundred only
5	Providing ruled pointing of coursed stone masonry with Cement mortar 1:3 20mm deep, after taking joints to depth of 20mm neatly lining, including cost of materials, labour, H.O.M of machineries curing etc., complete as per specification and directions of the Engineer-in-charge	Sqm	64.08	25.00	Rupees twenty five only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri K CHANNAKESHAVAMURTHY	
				Rate	Rate in Words
6	KSRB 4-1-6: Providing and laying in position plain cement concrete of mix M15 with cement @240kgs with 20mm and down size graded granite metal, coarse aggregate @0.878cum and fine aggregate @0.459 cum machine mixed, concrete laid in layers not exceeding 15 cms, thick well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	9.61	4700.00	Rupees four thousand seven hundred only
7	KSRB 4.2.2: Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 Kgs, with 20mm and down size graded granite metal coarse aggregates @0.878 cum and fine aggregates @ 0.459 cum, with superplastiser @ 3lit confirming to IS 9103-1999 Reaffirmed -2008, machine mixed, concrete laid in layers not exceeding 15 cms, thick vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills fillets etc, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	22.11	5300.00	Rupees five thousand three hundred only
8	KSRB 4.9-1: Providing T.M.T Steel reinforcement for RCC Work including straightening, cutting, bending hooking, placing in position, lapping and/or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No.KBS 4.6.3	Qnt.	0.80	7200.00	Rupees seven thousand two hundred only
9	KSRB 4-6-4: Providing and removing centering, shuttering, strutting propping etc, and removal of formwork for Vertical surface such as walls at any thickness including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications. Specification	Sqm	63.23	200.00	Rupees two hundred only
10	KSRRB M100-1 Loading and unloading of stone boulder/stone aggregates/sand/kankeer/moorum. KSRRB M100-1: Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications. MORTH Chapter	Cum	396.66	85.00	Rupees eighty five only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.